


BM 360152-1 Ryan CompaniesNEW_Medtronic T MEP_A2.rvt



SHEET NOTES

2. EXTEND RA MAIN DUCT TO OUTSIDE ROOM. PROVIDE TURNED UP ELBOW AT END OF RA DUCT.

GENERAL NOTES

1. REFER TO SHEET M.1-00 FOR LEGENDS, GENERAL NOTES AND ABBREVIATIONS.
2. ANY DUCTWORK OVER EXPOSED CEILING AREAS SHALL HAVE INTERNAL LINER AND SHALL BE PREPARED FOR PAINTING WITH PANTLOCK AND STICKERS REMOVED. REFER TO ARCH DRAWINGS FOR RCP INDICATING EXPOSED CEILING AREAS.
3. REFRIGERANT PIPE ROUTINGS SHOWN ARE DIAGRAMMATIC. CONTRACTOR TO COORDINATE AND DOCUMENT ALL VRF PIPING/WIRING SIZING, ROUTING AND LENGTHS WITH VRF MANUFACTURER AND VRF SYSTEM SUBMITTALS. TO ENSURE SYSTEM LIMITATIONS ARE NOT EXCEEDED AND PROPER REFRIGERANT CHARGE IS APPLIED FOR EACH SYSTEM. REFER TO SPLIT SYSTEM SCHEMATIC FOR MORE INFORMATION.
4. PROVIDE CABLE OPERATED REMOTE REGULATOR FOR ANY GRID DAMPER ABOVE INACCESSIBLE CEILING. ADJUSTMENT SHALL BE THROUGH DIFFUSER FACE.
5. MAINTAIN MINIMUM SEPARATION FROM OUTSIDE AIR INTAKES TO TERMINATIONS OF EXHAUST, COMBUSTION AIR, PLUMBING VENTS, ETC. AS REQUIRED BY CODE.
6. COORDINATE EQUIPMENT HOUSEKEEPING PAD DIMENSIONS AND LAYOUT WITH THE GENERAL CONTRACTOR BASED ON FINAL EQUIPMENT SIZES.
7. PROVIDE MANUAL BALANCE DAMPERS IN ALL SUPPLY DUCT BRANCH TAPS DOWNSTREAM OF VAV BOXES.
8. PROVIDE MANUAL BALANCE DAMPERS IN ALL EXHAUST DUCT BRANCH TAPS.
9. PROVIDE TRANSFER DUCTS IN FULL HEIGHT WALLS IN AREAS WHERE A PLENUM RETURN SYSTEM IS UTILIZED. BOOTS SHALL BE SIZED TO MAINTAIN A MAXIMUM OF 500 FPM.
10. COORDINATE SPACE TEMPERATURE SENSORS AND THERMOSTAT LOCATIONS TO ALIGN HORIZONTALLY WITH LIGHT SWITCHES. MOUNT AT 48" AFF.
11. TEMPERATURE CONTROLS CONTRACTOR SHALL SUBMIT PLANS INDICATING ALL SPACE TEMPERATURE SENSORS, T-STATS, HUMIDITY SENSORS, ETC. AS PART OF SUBMITTAL PROCESS FOR A/E REVIEW PRIOR TO ROUGH IN FOR REVIEW.
12. PROVIDE INSULATED BASEPLATES FOR T-STATS LOCATED ON EXTERIOR WALLS.

3300 S. HWY 287 - BUILDING 1
3500 S. HWY 287 - BUILDING 2
LAFAYETTE, CO 80026

Gensler

1225 17th Street
Suite 150
Denver, CO 80202
United States

Tel 303.595.5585
Fax 303.825.6823

WSP

WSP
5613 DTC Parkway
Suite 500
Greenwood Village, CO 80111
Tel 303.694.4755

COMPASS
GROUP

Compass Studio
1 Huntington Quadrangle
Suite 205
Melville, NY 11747

△	Date	Description
	11/20/2020	ISSUE FOR SCHEMATIC DESIGN
	02/26/2021	ISSUE FOR DESIGN DEVELOPMENT
	05/21/2021	ISSUE FOR PERMIT & CONSTRUCTION

Seal / Signature



Project Name

MEDTRONIC

Project Number

003.7799.000

Scale

1/8" = 1'-0"

Description

HVAC PLAN - BUILDING 1 - LEVEL 3 - SEGMENT A2

M.1-203-A2

© 2020 Gensler

KEY PLAN

